



Pool Safety is our Top Priority

## Testing & Set-up Verification Procedure



### Version 3.4

Proper operation of the SR-500 and SR-500 PS must be verified by restricting flow to the pump while running in any of the normal operating modes (timed, continuous, and remote). Begin testing by covering the main drain sump with a rubber mat. This will cause the pump to pull through the skimmer line(s) only, resulting in a higher operating vacuum. It may be possible to cover the drain and not increase the operating vacuum past the cut-off threshold. In these cases it will be necessary to close the skimmer valve(s) to create the vacuum necessary to create an alarm condition.

Note: Repeat this testing 3 times to verify proper installation.

Stingl Products recommends that Models SR-500 and SR-500PS units be tested monthly to insure proper operation, especially during pool and spa seasons.

---

### Stingl Products

PMB #325, 21010 Southbank Street Sterling, VA 20165  
Tel (571) 434.6010; (888) 749-5433 Fax (571) 434-6013  
[www.stinglproducts.com](http://www.stinglproducts.com)